Approved Qty	Description	Unit	Approved Tender Rates of A S MANI (S S ROAD DEVOLOPERS)		
			In Figures		In Words
118.4	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes etc complete as per specifications and directions of engineer in charge of the work	Sqm	432.0	51148.80	Rupees Four Hundred Thirty Two Only
				3816564.66	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

11/10

11/10

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT37106

APPROVED SCHEDULE - B

BTP/BBMP/E-PMT/11/2019-20, Date: 11.07.2019

rovements and Asphalting to Roads at Doddabommasandra and Surrounding areas in Ward No. 09 dyaranyapura) Vidyaranyapura Sub Division.

Approved Qty.	Description	Unit	Approved Tender Rates of A S MANI (S S ROAD DEVOLOPERS)		
			In Figures		In Words
461.97	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	231.69	107033.83	Rupees Two Hundred Thirty One and Sixty Nine Paise Only
2136.24	Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	105.74	225886.02	Rupees One Hundred Five and Seventy Four Paise Only
521.64	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	704.9	367704.04	Rupees Seven Hundred Four and Ninety Paise Only
1.8	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5137.71	9247.88	Rupees Five Thousand One Hundred Thirty Seven and Seventy One Paise Only
5.67	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5521.38	31306.22	Rupees Five Thousand Five Hundred Twenty One and Thirty Eight Paise Only
21.6	Providing ruled pointing 20 mm deep to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	142.99	3088.58	Rupees One Hundred Forty Two and Ninety Nine Paise Only
9	Providing precast slab of 250mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - (Data rate Approved).	Sqm	5147.1	46323.90	Rupees Five Thousand One Hundred Forty Seven and Ten Paise Only
344	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	930.47	320081.68	Rupees Nine Hundred Thirty and Forty Seven Paise Only
43.75	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, ncluding cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5459.95	238872.81	Rupees Five Thousand Four Hundred Fifty Nine and Ninety Five Paise Only
387	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	918.38	355413.06	Rupees Nine Hundred Eighteen and Thirty Eight Paise Only

Signature of the contractor

Executive Engineer

Approved Qty	Description	Unit	Approved Tender Rates of A S MANI (S S ROAD DEVOLOPERS)		
			In Figures		In Words
1075	Providing chamfering edges to stone slab 2.5 cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	m	58.41	62790.75	Rupees Fifty Eight and Forty One Paise Only
1542.75	Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by manual means without disturbing the base and stacking of the debris materials including cost of all labour charges etc complete as per specifications and directions of engineer in charge of the work	Sqm	90.63	139819.43	Rupees Ninety and Sixty Three Paise Only
368.19	Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1901.22	700010.19	Rupees One Thousand Nine Hundred One and Twenty Two Paise Only
1542.75	Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	34.24	52823.76	Rupees Thirty Four and Twenty Four Paise Only
42.26	Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixd material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.3 % VG-30 Bitumen etc complete as per specifications and directions of engineer in charge of the work	Cum	5273.66	222864.87	Rupees Five Thousand Two Hundred Seventy Three and Sixty Six Paise Only
2217	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	5.04	11173.68	Rupees Five and Four Paise Only
2217	Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	14.1	31259.70	Rupees Fourteen and Ten Paise Only
111.72	Providing and laying bituminous concrete 40 mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects complete as per specifications. MORTH Specification No. 509 - using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 45 mm) with 6 % VG-30 Bitumen etc complete as per specifications and directions of engineer in charge of the work	Cum	7516.25	839715.45	Rupees Seven Thousand Five Hundred Sixteen and Twenty Five Paise Only

nature of the contractor

Executive Engineer